WHS DOCUMENTS & TEMPLATES

DOC-CHP-FV · Wood Chipper Field Verification Checklist

Product Overview

For: Businesses whose workers feed and operate wood chippers: owners, supervisors, WHS advisers and workplace assessors

Version 1.0 · 9 November 2026

SAMPLE

An editable supervisor's checklist that checks, on site, that the controls for wood chipper are in place and working.

The supervisor looks at each control working, not at its paperwork, and marks each check Pass, Not met or N/A, with the evidence seen. ★ marks the critical controls, and a critical control that is Not met is escalated the same shift. The checklist also has questions for the people doing the work, an actions table with owners and due dates, a summary and sign-off.

It is the same checklist as in the Wood Chipper Safety & Competency Pack (DOC-CHP-PACK), word for word. The Wood Chipper VOC Assessment Template (DOC-CHP-VOC) and the Wood Chipper Safe Work Instruction Template (DOC-CHP-SWI) are also sold on their own. The Wood Chipper Safety & Competency Pack (DOC-CHP-PACK) contains them all: the safe work instruction, the wood chipper pre-start checklist, the VOC and the field verification, with a setup guide.

A document is not a control. The feed control bar, the emergency stops, the hopper guard, the second person and the competent operator are the controls. These documents describe them, check them, and record that they are working. A control must change the risk, and someone must be able to check it.

These documents support your business to manage risk and meet its WHS or OHS duties. They do not do that on their own. They are general templates: adapt them to your equipment, your site and your people, consult your workers, and check that the controls they describe are in place and working.

What is included

Item	File
Supervisor field verification checklist: feed control and emergency stop tests, feeding technique, two-person rule and exclusion zones	02_FIELD_VERIFICATION/Supervisor Field Verification Checklist.docx and .pdf
Setup note: what to adapt before use, and every placeholder	01_START_HERE/Setup Note.pdf
Start here: Read Me First, Product Overview, Permitted Use Terms, Version Information	01_START_HERE/ (four PDFs)

Who it is for

- Businesses whose workers feed and operate wood chippers
- Supervisors and managers who check that controls are working, on a set schedule and after a change or incident

© 2026 Orana Skills Centre. All rights reserved.

SAMPLE · Wood Chipper Field Verification Checklist · Buy the full editable version:
training.oranaskillscentre.com/documents/wood-chipper-field-verification-checklist

YOUR LOGO
Right-click > Change Picture

[Company name]

WHS DOCUMENTS & TEMPLATES · DOC-CHP-FV

Supervisor Field Verification Checklist

Wood chippers: feed control, emergency stops, no reaching in, two-person rule and exclusion zones

Site		**Areas checked**	
Date and time		**Shift**	
Verified by		**Equipment checked (IDs)**	

How to verify

- Visit the area while chipping is under way. Look at each control working, not at its paperwork.
- Mark each check Pass, Not met or N/A. Pass means you saw the control in place and working. If you did not see it, it is not a Pass.
- Write what you saw in the evidence column: a location, a photo reference, a record you sampled.
- Talk to the people doing the work, using the questions after the checks. They know where the near misses are.
- Record every Not met in the actions table, with an owner and a due date. Fix what you can on the spot, and record that too.

Escalate now

If a ★ critical control is Not met, act before you leave the area. Stop or restrict the chipping there until it is fixed or another control is in place, and tell **[Escalation contact]** the same shift. A failed critical control is a high potential incident: report it as one.

Checks

★ marks a critical control: one whose failure could let a person be drawn into the chipper or struck by its discharge. Delete checks that do not apply, and add your own.

No.	Look for (★ critical control)	Pass	Not met	N/A	What you saw (evidence)
Feed control and emergency stops					
1	The feed control bar and emergency stops were tested before use and work ★	☐	☐	☐	
2	Guards and the hopper are in place ★	☐	☐	☐	
Feeding					
3	Operators feed from the side and keep hands and body outside the hopper ★	☐	☐	☐	
4	No hands or feet used to push material ★	☐	☐	☐	
5	No loose clothing or gauntlet gloves ★	☐	☐	☐	
Two-person rule					
6	A second trained person is present while chipping ★	☐	☐	☐	

© 2026 Orana Skills Centre. All rights reserved.

SAMPLE · Wood Chipper Field Verification Checklist · Buy the full editable version:
training.oranaskillscentre.com/documents/wood-chipper-field-verification-checklist

WHS DOCUMENTS & TEMPLATES · DOC-CHP-FV

Wood Chipper Field Verification Checklist

END OF THE FREE SAMPLE

This sample shows a few pages, so you can judge the layout and the quality. An editable supervisor's checklist that checks, on site, that the controls for wood chipper are in place and working.

What the full product contains

- **Supervisor field verification checklist: feed control and emergency stop tests, feeding technique, two-person rule and exclusion zones**
  02_FIELD_VERIFICATION/Supervisor Field Verification Checklist.docx and .pdf
- **Setup note: what to adapt before use, and every placeholder**
  01_START_HERE/Setup Note.pdf
- **Start here: Read Me First, Product Overview, Permitted Use Terms, Version Information**
  01_START_HERE/ (four PDFs)

Formats

- Word (.docx), editable, with your logo and business name in the header
- PDF copy of the Word document, for printing blank
- Delivered as a single ZIP download

Get the full editable documents

https://training.oranaskillscentre.com/documents/wood-chipper-field-verification-checklist

Instant download after purchase. · Orana Skills Centre · 1800 231 173 · bookings@oranaskillscentre.com

© 2026 Orana Skills Centre. All rights reserved. · v1.0